


CB-12P INSTALLATION INSTRUCTIONS

244 Bergen Boulevard, Woodland Park, NJ 07424, Phone: 973.785.4347 - Fax: 973.785.4207

PRIOR TO CEILING INSTALLATION, DETERMINE MOUNTING LOCATION
OF THE FLANGE FOR THE PROJECTOR MOUNT. IF DEFAULT FACTORY
LOCATION WILL BE USED, PROCEED TO STEP 2. IF CHANGING TO
ALTERNATE LOCATION, FOLLOW STEPS 1a THRU 1b.

NOTE: FLANGE LOCATION CAN BE CHANGED AFTER CEILING INSTALLATION.


- 1a. REMOVE POLE MOUNT PLATE COVER (COVER SCREWS LOCATED IN INTERIOR OF CEILING BOX).
- 1b. REMOVE FLANGE AND MOVE TO ALTERNATE LOCATION. CHANGE PLUG LOCATION ON THE POLE MOUNT PLATE COVER AS REQUIRED, AND RE-INSTALL THE PLATE COVER WITH THE (2) ORIGINAL SCREWS.



43189 LIT1317B


- INSTALL 10-3/4" x 15-1/4" DROP CEILING PANEL MATERIAL INTO DOOR OF CB-12P. BEND CAPTURE TABS OVER PANEL TO HOLD PANEL IN PLACE.
- 4. REMOVE SHELF AND MOUNT ELECTRONICS TO SHELF. USE HOLE/SLOT PATTERN ON SHELF TO MOUNT EQUIPMENT. ADDITIONAL HOLES MAY BE REQUIRED. RE-INSTALL SHELF INTO CB-12P. MAKE ELECTRICAL CONNECTIONS AS REQUIRED.

NOTE: MAXIMUM LOAD PER SHELF - 20 LBS EACH



5. INSTALL PROJECTOR MOUNT PIPE INTO CB-12P. SECURE PIPE WITH SET SCREW. FINISH INSTALLATION PER MANUFACTURER'S PROJECTOR MOUNT INSTRUCTIONS.

NOTE: MAXIMUM PROJECTOR LOAD INCUDING MOUNTED ACCESSORIES - 50 LBS



FSR Inc.

244 Bergen Boulevard, Woodland Park, NJ 07424 Phone: 973.785.4347 - Fax: 973.785.4207 Web: www.fsrinc.com - E-mail: sales@fsrinc.com